

La Brea Station Decking Overview

Decking

- On Wilshire, between Orange Dr. and Detroit St.
- Construction of a concrete deck, curb to curb
- Sidewalks be maintained, or pedestrian detours created
- Decking will serve as the temporary street surface
- Traffic will travel on the installed deck panels while the station is constructed underground
- La Brea Station:
 - Approx. 1,000 feet long
 - Approx. 70 feet wide
 - Approx. 60 feet deep
- Will follow pile operations; anticipated to begin June 2016
- **Will work closely with First Responders on emergency access and safety**
- **Pending Board of Public Works approval in May**
- **Additional activities under decking closures: jet grouting, piling, temp. civil improvements.**



La Brea Station Decking Schedule

*Dates and work activities subject to change

June 2016 through Fall 2016

Approximately 22 weekend closures (no work 4th of July or Labor Day weekends)

Work is scheduled in three phases.

Phase 1: Wilshire-Detroit to La Brea

Phase 2: Wilshire/La Brea Intersection

Phase 3: Wilshire-La Brea to Highland

Traffic Plan for closures

- Fridays 10am: Wilshire reduced to one lane each direction
 - Lane reductions at 10am will allow us to start the loudest work (breaking of concrete) during day time hours.
- Friday 8pm: Full closure of Wilshire or Wilshire/La Brea intersection (Phase 2)
- Monday 6am: Streets open
- Work occurs 24/7

For information on closures and detours

WWW.METRO.NET/PURPLELINEEXT



Metro®